

Information Series 125

Paver Operations for Quality



ASPHALT
100% RECYCLABLE

www.hotmix.org

This publication is provided by the Members of the National Asphalt Pavement Association (NAPA), who are the nation's leading Hot Mix Asphalt (HMA) producer/contractor firms and those furnishing equipment and services for the construction of quality HMA pavements.

NAPA Members are dedicated to providing the highest quality HMA paving materials and pavements, and to increasing the knowledge of quality HMA pavement design, construction, maintenance and rehabilitation. NAPA also strongly supports the development and dissemination of research, engineering and educational information that meets America's needs in transportation, recreational, and environmental pavements.



NAPA Building • 5100 Forbes Blvd. • Lanham, MD USA 20706-4407
Tel: (301) 731-4748 • Fax: (301) 731-4621
www.hotmix.org

This publication is designed to provide information of interest to NAPA Members and is not to be considered a publication of standards or regulations. The views of the authors expressed herein do not necessarily reflect the decision making process of NAPA with regard to advice or opinions on the merits of certain processes, procedures, or equipment.

COPYRIGHT NOTICE

Publications produced and published by the National Asphalt Pavement Association (NAPA) are copyrighted by the Association and may not be republished or copied (including mechanical reproductions) without written consent. To obtain this consent, contact the Association at the address given in this publication.

© 1996 National Asphalt Pavement Association

Information Series 125
Printed 6/1996
Revised 10/2002

Paver Operations For Quality

Contents

1. Introduction.....	1
2. HMA Materials	2
2.1. Asphalt Cement	2
2.2. Mix Temperature.....	2
2.3. Mix Gradation.....	2
2.4. Aggregate Size in Relation to Paving Depth.....	2
2.5. SMA and Superpave Mix Designs	2
3. Understanding the Paver.....	3
3.1. Paver Basics	3
3.2. Paver Speed	4
3.3. Head of Material.....	6
3.3.1. Head of Material Too Low.....	6
3.3.2. Head of Material Too High.....	6
3.3.3. Controlling the Head of Material	7
3.3.3.1. Paver Speed.....	7
3.3.3.2. Feeder Sensors	8
3.3.3.3. Variable Width Paving.....	10
3.3.3.4. Auger Height.....	10
3.3.3.5. Auger Speed.....	10
3.3.4. Screed.....	11
3.3.4.1. Angle of Attack.....	11

4.	Automatic Screed Controls	12
4.1.	General.....	12
4.2.	References.....	13
4.2.1.	Stringline.....	13
4.2.2.	Floating Beam Reference	14
4.2.3.	Joint-Matching Shoe	14
4.2.4.	Laser	14
4.3.	Grade Controls and Sensors	15
4.4.	Modes of Operation	15
4.4.1.	Grade and Slope	15
4.4.2.	Dual Grade Controls.....	15
4.5.	Selecting Methods of Grade Sensing and Mounting Location of the Grade Sensor	15
5.	Planning	16
6.	Surface Preparation	17
6.1.	Subgrade and Aggregate Base	17
6.1.1.	Milling.....	17
6.1.2.	Repairing and Patching Failed Areas	18
6.1.3.	Repairing and Filling Cracks	19
6.1.4.	Leveling Existing Surface	19
6.1.5.	Cleaning Existing Surface.....	19
6.1.6.	Prime and Tack Coat Application.....	19
7.	Paving.....	20
7.1.	Quality Procedures in the Asphalt Paving Process	20
7.2.	Proper Loading of the Haul Trucks	20
7.3.	Transporting HMA to the Paver	20
7.4.	Unloading HMA to the Paver Hopper.....	21
7.4.1.	Direct Truck Discharge into Paver Hopper.....	21
7.4.2.	Using Material Transfer Machines Between the Truck and Paver	22
7.4.3.	Windrow Elevators and Belly Dump Trucks	22
7.4.4.	Other Non-Self Propelled Material Transfer Devices	22
7.4.5.	Self Propelled Material Transfer Vehicles	23

7.5.	Moving HMA Through the Paver.....	23
7.5.1.	Corner of Hopper Wings – Area #1	23
7.5.2.	Center of Hopper – Area #2.....	24
7.5.3.	Front Outside Corners of the Hopper – Area #3	24
7.5.4.	Material Spillage – Area #4.....	24
7.5.5.	Material Movement In and Around Auger Drive Box – Area #5.....	24
7.5.6.	Material Movement In and Around Bearing Pedestals – Area #6	25
7.5.7.	Hopper Area Using Material Transfer Insert	25
7.5.8.	Outer Edges of Conveyor Chains – Area #7.....	25
7.5.9.	Outside Edge of the Screed – Area #8	25
8.	Screeding for Mat Quality.....	26
8.1.	Angle of Attack.....	26
8.2.	Screed Strike-off.....	26
8.3.	Screed Counterbalance.....	26
8.4.	Screed Crown.....	27
9.	Joint Construction	27
9.1.	Transverse Joints.....	28
9.1.1.	End Joints	28
9.1.1.1.	End of Paving Butt Joint	28
9.1.1.2.	Adjoining Butt Joint	28
9.1.1.2.1	Lower Lifts	28
9.1.1.2.2	Surface Lift.....	29
9.1.1.3.	Tapered Joint	29
9.1.2.	Restart of Paving Joint.....	29
10.	Longitudinal Joints.....	30
10.1.	First Pass.....	30
10.2.	Second Pass.....	31
11.	Identifying and Correcting Mat Defects.....	31
	Appendix A: Paving Crew Responsibilities	32